



SEE DRAWING 4749-D1-DIV

Traffic Management Notes

- 1) All temporary traffic management shall be in accordance with chapter 8 of the Traffic Signs Manual 2009.
- 2) All temporary traffic management shall be in accordance with the Traffic Signs Regulations and General Directions 2016
- 3) All temporary traffic management shall conform to the Safety at Street Works and Road Works, a code of Practice 2013.
- 4) All temporary traffic management signs should be located 450mm minimum from the kerb face.
- 5) All temporary traffic management sign locations are indicative and are subject to a on-site approval from the Engineer.

This drawing has been produced for the specific client and project identified below and is not intended for the use by any other person or for any other purpose (c) Fenton TM specialists.
 This drawing is a representation of the traffic management systems, which must be installed by qualified personnel. Distances between signs may NOT be to scale for purposes of clarity.
 On installations Taper lengths, Safety zones, Minimum Visibility to first sign & Minimum size of Signs & Cones will conform to Chp8 Guidelines for the speed of the road.

KEY

- Stage area
- Safety zone
- 1m Road cones
- Emergency access
- Traffic Head
- Aspect of sign view
- Pedestrian barrier
- Pedestrian Walkway
- No parking cones
- Flashing beacons
- Gateman

Fenton TM Address:

Site Address:

Speed of Road:

Drawing Number: 4749-D1



Unit 29-30
Shangri-La Farm,
Todds Green,
SG1 2JE

High St, Ware SG12 9AP



Scale @A3 N/A Date Drawn: 07.03.24

Works Date: TBC Drawn By: CM Checked By: CKM

Notes: